

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

SR #	DESCRIPTION	TAKEOFF QUANTITY			
		Quantity	Unit	Quantity	BF/SF
	WOOD, PLASTIC & COMPOSITE				
	WALL FRAMING				
	GARAGE				
	2"x6" Exterior Wall Framing				
1	2x6x104-5/8"H Studs @ 16"	76	EA	684	BF
2	2X6X16' L Bottom sill plate P.T.	7	EA	112	BF
3	2X6X16' L Top double plate & Mid span blocking	19	EA	304	BF
	Exterior Wall Sheathing				
4	(4' X 9'X 1/2") O.B.S Exterior wall sheathing Note: Size of Wall sheathing assumed, not shown on plans. Please Confirm & VIF.	25	EA	887	SF
	2"x4" Interior Garage to House Wall Framing				
5	2x4x104-5/8"H Studs @ 16"	25	EA	150	BF
6	2X4X16' L Bottom sill plate P.T.	2	EA	21	BF
7	2X4X16' L Top double plate & Mid span blocking	6	EA	64	BF
	2"x4" Interior Wall Framing				
8	2x4x104-5/8"H Studs @ 16"	19	EA	114	BF
9	2X4X16' L Bottom sill plate P.T.	2	EA	21	BF
10	2X4X16' L Top double plate & Mid span blocking	5	EA	53	BF
	Level 01				
	2"x6" Exterior Wall Framing				
11	2x6x104-5/8"H Studs @ 16"	193	EA	1737	BF
12	2X6X16' L Bottom sill plate P.T.	16	EA	256	BF
13	2X6X16' L Top double plate & Mid span blocking	48	EA	768	BF
	2"x6" Exterior Gable Wall Framing				
14	2x6x104-5/8"H Studs @ 16"	66	EA	594	BF
15	2X6X16' L Bottom sill plate P.T.	11	EA	176	BF
16	2X6X16' L Top double plate & Mid span blocking	32	EA	512	BF
	Exterior Wall Sheathing				
17	(4' X 9'X 1/2") O.B.S Exterior wall sheathing Note: Size of Wall sheathing assumed, not shown on plans. Please Confirm & VIF.	64	EA	2296	SF
	Exterior Gable Wall Sheathing				
18	(4' X 9'X 1/2") O.B.S Exterior wall sheathing Note: Size of Wall sheathing assumed, not shown on plans. Please Confirm & VIF.	16	EA	560	SF
	2"x4" Interior Wall Framing				
19	2x4x104-5/8"H Studs @ 16"	192	EA	1152	BF
20	2X4X16' L Bottom sill plate P.T.	16	EA	171	BF
21	2X4X16' L Top double plate & Mid span blocking	48	EA	512	BF
	2"x6" Interior Wall Framing				
22	2x6x104-5/8"H Studs @ 16"	7	EA	63	BF
23	2X6X16' L Bottom sill plate P.T.	1	EA	16	BF
24	2X6X16' L Top double plate & Mid span blocking	2	EA	32	BF
	Level 02 (Bonous Room)				
	2"x6" Exterior Wall Framing				
25	2x4x104-5/8"H Studs @ 16"	76	EA	456	BF
26	2X4X16' L Bottom sill plate P.T.	7	EA	75	BF
27	2X4X16' L Top double plate & Mid span blocking	19	EA	203	BF

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

SB #	DESCRIPTION	TAKEOFF QUANTITY			
	Exterior Wall Sheathing				
28	(4' X 9' X 1/2") O.B.S Exterior wall sheathing Note: Size of Wall sheathing assumed, not shown on plans. Please Confirm & VIF.	25	EA	888	SF
	2"x4" Interior Wall Framing				
29	2x4x104-5/8"H Studs @ 16"	18	EA	108	BF
30	2X4X16' L Bottom sill plate P.T.	2	EA	21	BF
31	2X4X16' L Top double plate & Mid span blocking	5	EA	53	BF
	Headers/ Beam For Opening				
32	2x8x16'L Header @ Doors	12	EA	265	BF
33	2x8x16'L Header @ Window	14	EA	299	BF
	Note: Size of header assumed for takeoffs as no sizes shown on drawings. Please confirm & VIF.				
	Interior Trim Board @ Opening				
34	1 X 4 X 12' L Wood Trim @ Doors	894	LF	75	Pcs
35	1 X 4 X 12' L Wood Trim @ Window	517	LF	43	Pcs
	FLOOR FRAMING				
	Floor Joists:				
	16" Deep Wood "1" Floor Joists @ 16" O.C.				
36	Wood Floor "1" joists @ 10'	2	EA	2	Pcs
37	Wood Floor "1" joists @ 18'	2	EA	2	Pcs
38	Wood Floor "1" joists @ 30'	21	EA	21	Pcs
	Floor Sheathing:				
39	3/4" T&G Floor sheathing Size: 4'0"x8'0"	30	EA	962	SF
	Note: Size of Floor Sheathing assumed for takeoffs as no sizes shown on drawings. Please confirm & VIF.				
	Wood Beam:				
40	2X10X16'L Wood Beam	19	EA	507	BF
	Wood Post:				
41	8 x 8 Wood Post (9' H) @ Patio	3	EA	3	Pcs
42	12 x 12 Wood Post (9' H) @ Porch	4	EA	4	Pcs
	Wood Blocking				
43	2x12x16' L Rim board	4	EA	132	BF
	CEILING FRAMING				
	Level 01				
	Ceiling Joist				
	2x10 Ceiling Joist @ 16" O.C. For Front Porch				
44	2x10 Ceiling joist @ 8' L	12	EA	12	Pcs
45	2x10 Ceiling joist @ 10' L	7	EA	7	Pcs
	2x10 Ceiling Joist @ 16" O.C. For Patio				
46	2x10 Ceiling joist @ 12' L	1	EA	1	Pcs
47	2x10 Ceiling joist @ 14' L	28	EA	28	Pcs
	2x10 Ceiling Joist For Bedroom				
48	2x10 Ceiling joist @ 12' L	1	EA	1	Pcs
49	2x10 Ceiling joist @ 14' L	14	EA	14	Pcs
50	2x10 Ceiling joist @ 20' L	12	EA	12	Pcs
	2x10 Ceiling Joist For Master Bedroom				
51	2x10 Ceiling joist @ 16' L	9	EA	9	Pcs
52	2x10 Ceiling joist @ 18' L	13	EA	13	Pcs

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

SB #	DESCRIPTION	TAKEOFF QUANTITY			
	2x10 Ceiling Joist For Grate Room				
53	2x10 Ceiling joist @ 10' L	12	EA	12	Pcs
54	2x10 Ceiling joist @ 12' L	26	EA	26	Pcs
	2x10 Ceiling Joist For Kitchen				
55	2x10 Ceiling joist @ 14' L	18	EA	18	Pcs
	2x10 Ceiling Joist For Laundry				
56	2x10 Ceiling joist @ 10' L	8	EA	8	Pcs
57	2x10 Ceiling joist @ 12' L	2	EA	2	Pcs
58	2x10 Ceiling joist @ 14' L	12	EA	12	Pcs
	Level 02 (Bonous Room)				
	2x10 Ceiling Joist For Laundry				
59	2x10 Ceiling joist @ 4' L	3	EA	3	Pcs
60	2x10 Ceiling joist @ 10' L	7	EA	7	Pcs
61	2x10 Ceiling joist @ 18' L	20	EA	20	Pcs
	Ceiling Beam				
62	2x10X16'L Ceiling Beam	2	EA	2	Pcs
63	(3) 1-3/4" X 10" LVL Beam (3/16)	48	LF	3	Pcs
64	(3) 1-3/4" X 10" LVL Beam (3/26)	78	LF	3	Pcs
	ROOF FRAMING				
	Roofing Rafter				
	2 x 8 Roof Rafter @ 16" O.C. (Pitch 3/12)				
65	2 x 8 Roof Rafter @ 12' L	3	EA	3	Pcs
66	2 x 8 Roof Rafter @ 14' L	8	EA	8	Pcs
	2 x 8 Roof Rafter @ 16" O.C. (Pitch 9/12)				
67	2 x 8 Roof Rafter @ 4' L	23	EA	23	Pcs
68	2 x 8 Roof Rafter @ 6' L	27	EA	27	Pcs
69	2 x 8 Roof Rafter @ 8' L	20	EA	20	Pcs
70	2 x 8 Roof Rafter @ 10' L	12	EA	12	Pcs
71	2 x 8 Roof Rafter @ 12' L	18	EA	18	Pcs
72	2 x 8 Roof Rafter @ 14' L	19	EA	19	Pcs
73	2 x 8 Roof Rafter @ 16' L	12	EA	12	Pcs
74	2 x 8 Roof Rafter @ 18' L	17	EA	17	Pcs
75	2 x 8 Roof Rafter @ 20' L	83	EA	83	Pcs
76	2 x 8 Roof Rafter @ 22' L	7	EA	7	Pcs
77	2 x 8 Roof Rafter @ 24' L	10	EA	10	Pcs
78	2 x 8 Roof Rafter @ 26' L	20	EA	20	Pcs
	2 x 8 Roof Rafter @ 28' L		EA	0	Pcs
	Roofing Outrigger				
	2 x 4 Outrigger @ 16" O.C.				
79	2 x 4 Outrigger @ 4' L	49	EA	49	Pcs
80	2 x 4 Outrigger @ 6' L	30	EA	30	Pcs
	Roof Sheathing				
81	1/2" CDX Plywood Roof sheathing (4'0"x8'0")	177	EA	5667	SF
	Note: Size of Roof Sheathing assumed for takeoffs as no sizes shown on drawings. Please confirm & VIF.				
	Roof Beam				Pcs
82	2X8X16' Ridge beam	22	EA	22	Pcs
83	2X8X16' Hip beam	10	EA	10	Pcs
84	2X8X16' Valley beam	21	EA	21	Pcs
	HARDWARE				

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

SB.#	DESCRIPTION	TAKEOFF QUANTITY			
85	5/8"x14" Headed anchors @ 32" O.C	385	EA	385	Pcs
86	Simpson LSTA 18	385	EA	385	Pcs
87	Simpson MST 12 @ 24" O.C	495	EA	495	Pcs
88	Simpson post top cap (8X8 Post)	3	EA	3	Pcs
89	Simpson post sill (8X8 Post)	3	EA	3	Pcs
90	Simpson post top cap (12X12 Post)	4	EA	4	Pcs
91	Simpson post sill (12X12 Post)	4	EA	4	Pcs
92	Simpson Hanger @ Ceiling joist	410	EA	410	Pcs
93	Simpson Hanger @ Roof joist	558	EA	558	Pcs
94	2-1/2" Ring shank nails @ Board & batten Siding	3605	EA	3605	Pcs
95	Nailing @ Furring strips	560	EA	560	Pcs
96	Nailing @ Wall sheathing	9030	EA	4	Box
97	Nailing @ Floor sheathing	2100	EA	1	Box
98	Nailing @ Roof sheathing	12390	EA	5	Box
99	Nailing @ Asphalt shingle roofing	9445	EA	2	Box
100	2 -1/4-inch-long 15-gauge nails @ PVC Fascia	192	EA	1	Box
101	2 -1/4-inch-long 15-gauge nails @Trim & Frieze Board	985	EA	1	Box
102	Misc. nailing for framing, sheathing etc.	1	LS	1	LS
THERMAL & MOISTURE PROTECTION					

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

ID #	DESCRIPTION	TAKEOFF QUANTITY			
INSULATION					
Level 01					
103	Batt insulation (R-13) For Exterior Wall	3183	SF	3183	SF
104	Batt insulation (R-13) For Exterior Gable Wall	560	SF	560	SF
105	Batt insulation For Floor	962	SF	962	SF
106	Batt insulation (R-13) For Ceiling	4181	SF	4181	SF
Level 02 (Bonous Room)					
107	Batt insulation (R-13) For Exterior Wall	888	SF	888	SF
108	Batt insulation For Floor	962	SF	962	SF
109	Batt insulation (R-13) For Ceiling	608	SF	608	SF
VAPOUR BARRIER					
Level 01					
110	Tyvek Building Wrap For Exterior Wall 10 Sq. Roll	3183	SF	4	Roll
111	Tyvek Building Wrap For Exterior Grable Wall 10 Sq. Roll	560	SF	1	Roll
Level 02 (Bonous Room)					
112	Tyvek Building Wrap For Exterior Wall 10 Sq. Roll	888	SF	1	Roll
EXTERIOR FINISHES					
Board & Batten					
113	(12" Wide X 12' H) Hardie Board Siding	333	Pcs	3997	SF
114	(1"X3"X12' H) Batten	388	EA	388	Pcs
115	(1"X2"X16' H) Furring strips	70	EA	70	Pcs
Trim Board					
116	1 X 4 X 12' L Wide Corner Trim	176	LF	16	Pcs
ROOFING					
Shingle Roofing					
117	(12" W X 36" L) 3D Arch Asphalt Shingles	1889	EA	5667	SF
118	Hip & Ridge Shingles (36.5 LF /Bundle)	245	LF	7	Bundles
119	(4' W X 250' L) #30 Felt for Underlayment 10 Sq. Roll	5667	SF	6	Rolls
120	(3' W X 67' L) Ice & Water Shield 2 Sq. Roll	1635	SF	9	Rolls
Roofing Flashing					
121	(2' Wide x 10' Long) Valley Flashing	164	LF	17	Pcs
122	(2' Wide x 10' Long) Hip Flashing	77	LF	8	Pcs
123	(2' Wide x 10' Long) Step Flashing	53	LF	6	Pcs
124	(2' Wide x 10' Long) Wall To Roof Joint Flashing	23	LF	3	Pcs
Fascia & Frieze Board					
125	(2"X 8"W X 12'L) Vinyl Fascia	381	LF	32	Pcs
126	(2"X6"X12') Sub Fascia	381	LF	32	Pcs
127	(1"X6"X12') Hardie Frieze Board	381	LF	32	Pcs
Soffit					
128	(12"W X 12' L) Vented Vinyl Soffit (206 LF)	206	SF	18	Pcs
129	(8"W X 12' L) Vented Vinyl Soffit (54 LF)	36	SF	5	Pcs
130	(8"W X 12' L) Solid Vinyl Soffit (122 LF)	82	SF	11	Pcs
Roofing Accessories					
131	Cobra Ridge Vent (4' L) Note: Assumed quantity. Please confirm & VIF.	164	LF	25	Pcs
FINISES					
DRYWALL ASSEMBLIES					
Level 01					
Exterior Wall					

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID: N/A

Scope: COMPREHENSIVE



Date: 08/07/22

ID #	DESCRIPTION	TAKEOFF QUANTITY			
132	5/8" Th. 1 Layer GWB on one side Size: 4'0"x9'0"	89	EA	3183	SF
133	5/8" Th. 1 Layer GWB on one side for Gable wall Size: 4'0"x9'0"	16	EA	560	SF
	Interior Wall				
134	5/8" Th. 1 Layer GWB on both side Size: 4'0"x9'0"	173	EA	6226	SF
	Ceiling Drywall				
135	1/2" Th. Ceiling Gypsum Board For Garage Size: 4'0"x8'0"	31	EA	961	SF
136	1/2" Th. Ceiling Gypsum Board For Porch & Patio Size: 4'0"x8'0"	24	EA	747	SF
137	1/2" Th. Ceiling Gypsum Board Size: 4'0"x8'0"	78	EA	2474	SF
	Level 02 (Bonous Room)				
	Exterior Wall				
138	5/8" Th. 1 Layer GWB on one side Size: 4'0"x9'0"	28	EA	977	SF
	Interior Wall				
139	5/8" Th. 1 Layer GWB on both side Size: 4'0"x9'0"	13	EA	446	SF
	Ceiling Drywall				
140	1/2" Th. Ceiling Gypsum Board Size: 4'0"x8'0"	19	EA	608	SF

Note:

1. Wastage of 10% is figured with all quantities,
2. We have assume building is in high wind area, we have taken 210 Nails per 1 SQ. Please Confirm & VIF.
3. Roof ridge vent quantity assumed. Please confirm on site.
4. Assumed 12' Long Vinyl Soffit.(Verify Size)
5. 3/4" T&G Floor sheathing assumed. VIF
6. 5/8" Roof sheathing assumed. VIF
7. Simpson hold-down quantity assumed, as hold-down shown on plans. Please confirm & VIF.
8. Simpson hangers are assumed @ Roof rafter on both side. Please confirm & VIF.
9. Roof gutter is Excluded as Not Mention In Drawings. VIF.
10. Joist spacing is not define on plans, we have assumed 16" O.C. Please confirm & VIF.
11. We have assumed interior trims @ opening w/ size of 1"x4"x12'Long. Please confirm & VIF.
12. We have assumed 3000 nails per box for siding & sheathing
13. We have assumed 7200 nails per box for roofing material